

Murphy's Masonry Ltd.
4-168 Barton St. Suite #301
Stoney Creek ON L8E4V6
647-865-3902
info@murphymasonry.ca
GST/HST Registration No.:
760760488RT0001



Estimate

ADDRESS

Church St. E. 27 - Sean
Malachi

ESTIMATE # 6225

DATE 01/04/2025

ACTIVITY	TAX	AMOUNT
Brick repair -Set up scaffold to access any high areas as needed -Lay out tarps to protect all work areas -Demo any spalling bricks at the front, left and right side of the building up to 150 bricks -Clear these areas of all dust and debris -Install new bricks that match as close as possible to the rest of the house -Grind/chip out any failing mortar joints in these same areas around the house including the foundation -Install new mortar that matches as close as possible to the rest of the house -Full clean up of job site -Dispose of all waste at an authorized waste facility If any additional bricks are needed to be replaced it will be \$30 plus HST per brick	HST ON	13,500.00
Porch Steps -Remove the existing wooden steps from the front of the porch -Dig down and excavate the area 8 inches -Install 4 inches of gravel and tamp firmly -Form where needed with lumber and install new 4 inch concrete pad for the new garden steps to sit on -Once the concrete has set up install 3 new garden stone steps to the area -Ensure all steps are level and slope away from the house -Full clean up of job site -Dispose of all waste at an authorized waste facility Approx Cost of the Indiana limestone steps 3 pieces and side fillers is \$1,500 plus HST this is not	HST ON	2,500.00

ACTIVITY	TAX	AMOUNT
----------	-----	--------

included in the line item amount. If the steps cost more the additonal cost will be added on.

<hr/>		
	SUBTOTAL	16,000.00
	HST (ON) @ 13%	2,080.00
	TOTAL	\$18,080.00

Accepted By

Accepted Date